3. The tender should be forwarded so as to reach the Chief Commandant's Office on or before Saturday the 29th March 1919, after which no tender will be received.

4. The tender should show the rates at which the different articles required can be supplied. Samples of materials to be used should accompany the tender. 759

5. The Chief Commandant reserves to himself the right of accepting or rejecting any tender without assigning any reason therefor.

6. The tender should be accompanied with a deposit of Rs. 100 in currency notes. If the tender is accepted and the tenderer fails to undertake the contract, he will forfeit the amount. If the tender is not accepted, the amount will be returned to the tenderer.

7. The successful competitor whose tender is accepted will be required to deposit Rs. 200 as security and to execute an agreement for the due fulfilment of the contract.

8. The Superintendent of the Government Stables will indent on the contractor for the supply of the clothing noted below which should be supplied within eight days of the acceptance of the tender.

9. The contractor's bills should be submitted by the Superintendent, to this office, for payment.

10. Should the contractor fail to comply with any of the conditions detailed above, the contract will be forthwith cancelled and the deposit credited to Government.

11. Sample of clothing can be seen in the Office of the Superintendent, Government Stables, Bangalore.

Description of articles	Probable number required	Maximum cost Rs. a. p.
Khaki suits for coachmen	36 each ...	7 8 0
Boots, pairs do	36 " ...	6 6 0
Khaki mull pugadies for coachmen	36 " ...	2 10 0
Blue mull pugadies do	36 " ...	2 10 0
Khaki suits for syces	36 " ...	5 10 0
Blue serge patties for syces (pair)	36 per pair ...	1 9 6
Khaki mull pagadies do	36 each ...	2 10 0
Blue mull pagadies do	36 " ...	2 10 0

Note—In the case of coachmen the suits include long coats and in the case of syces, they include short coats.

R. PUTTANNA,
Personal Assistant
to the Chief Commandant, Mysore State Troops
(in charge of current duties).

TUMKUR DISTRICT.

Dated——*March* 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Deputy Commissioner, Tumkur District, up to 10th April 1919, for restoring Kaggaladu minor tank Register No. 147, Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1319.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur District, between the hours of 11 A.M. and 5 P.M.

3. The tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Kaggaladu Tank Registered No. 147, Sira Taluk," in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Kaggaladu, minor tank Registered No. 147 of Sira Taluk :—

760

Items of work	Per	Quantity
Bund at R. L. 54·00—		
Picking the surface of the old bund to serve as a foundation for new earth ...	Sq. yard.	1,376
Turfing to slopes	,,	3,635
Earthwork including watering and tamping	C. yd.	3,925
Old stone work with ¼ new jelly	,,	107
New rough stone work with jelly	,,	615
New grade stones with chiselling figures and painting	Each	22
New register No. stone do do	,,	1
New bench mark stones do do	,,	2
Gauge stones do do	,,	1
Jungle clearing (jolly trees)	Lump	sum
Sluice at R. L. 45·65 —		
Cut opening the bund and refixing the same quantity, repairing the sluice tunnel to half its length if necessary raising works of walls both the front and rear cisterns.	Lump	sum
Minor distributary channel —	Lump	sum
Weir right (natural at R. L. 50·00) 150' long—		
Pitching stones in depressed portions of natural weir and levelling the site and constructing a wing wall, *i.e.*, pitching to bund side to prevent the scouring action of water.	Lump	sum

Dated——March 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Deputy Commissioner, Tumkur District, up to 10th April 1919, for restoring Handimalaku tank Registered No. 86, of the Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur District, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Handimalaku tank, Registered No. 86, Sira Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be return ed

Abstract estimate for restoring Handimalaku tank, Registered No. 86, Sira Taluk :—

Items of work	Per	Quantity
Bund at R. L. 58·00—		
Earthwork to bund including watering and tamping, etc., complete ...	C. yd.	3,411
Turfing to slopes	S. yd.	2,689
Old stone work with ¼ new jelly	C. yd.	100
Gravel backing behind revetment	,,	27
New rough stone work (lead 4 miles) ...	,,	259
Jungle clearing	Lump	sum
Refixing old grade stones with painting figures, etc., complete	Each	6
Do do new grade stones ...	,,	4
Index stone	,,	10
Bench mark stone	,,	2
Register No. stone	,,	1
Gauge stone	,,	1
Constructing masonry core wall to the old weir gap proposed to be filled up ...	Lump	sum
Sluice at R. L. 45·56—		
Repairing the existing front and rear cisterns of the sluice and if necessary the sluice also.	Lump	sum
Weir 75 ft. long at R. L. 53·00—		
Approach clearing (hard gravel and chattu)	C. yd.	166
Draft clearing hard gravel and chattu	,,	212
Earthwork foundation for weir (chattu soil)	,,	32
Benching foundation for body wall and retaining wall on rock ...	Lump	sum
Burnt brick in surki mortar	C. ft.	839
Burnt stone slabs dressed	S. ft.	219
Plastering with Surki mortar	Sq.	2·00
Rough stone work utilising old material	C. yd.	100
Stone jaggles for coping of body and toe wall	Each	20
Blasting rock in draft and approaches	Lump	sum

Dated——March 1919. 761

Notice is hereby given that sealed tenders will be received at the Office of the Deputy Commissioner, Tumkur District, up to 10th April 1919, for restoring Kundur tank Registered No. 6 of the Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur District, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Kundur tank Registered No. 6, Tumkur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Kundur tank, Registered No. 6, Tumkur Taluk :—

Items of work	Per	Quantity
Bund at R. L. 55·50, top width 4½ ft.—		
Earthwork to bund including watering and tamping, etc., complete ...	C. yd.	4,686
Turfing to earth slopes	Sq. yd.	3,459
Resetting old stone revetment	Lump	sum
New stone revetment	C. yd.	400
Cutting figures and painting to old grade stones	Each	10
New grade stones including cutting figures and painting, etc., complete ...	,,	7
New register No. stones	,,	1
New gauge stone	,,	1
New B. M. stones	,,	2
Sluice—		
Repairing the existing masonry sluice and cistern	Lump	sum
Weir 100 ft. long to the left at R. L. 50·00—		
Earthwork, dismantling the damaged body wall and wings, cutting the bund and excavating foundation for the new bodywall.	Lump	sum
Burnt brick in surki mortar	C. ft.	1,087
Burnt stone slabs dressed	Sq. ft.	307
Plastering with surki mortar	Sq.	3
Rough stone work new	C. yd	115

Notification dated 7th March 1919.

It is notified for general information that the undermentioned Government unoccupied lands (to be assessed at dry rates) in the Ankasandra Amrut Mahal Kaval, Chiknayakanhalli Taluk, each measuring between 4 and 6 acres will be sold by public auction on the spot by the Deputy Commissioner, Tumkur District, or by one of the Assistant Commissioners, deputed by him on the 15th, 16th and 17th April 1919. The intending bidders may present themselves at the time of sale and bid for the lands. The auction purchasers, must be bound to abide by the rules prescribed for malki sales and they should also be liable to pay the assessment fixed by the Survey Superintendent from 1919-20.

Block No.	Total survey number in block	Boundaries of the block
1	94	*East.*—Limits of Bevinahalli and Ankasandra villages. *West.*—Limits of Oopparahalli and Otikere villages. *South.*—Limits of Bevinahalli village. *North.*—Limits of Barapur village.

A. SUBRAMANYA IYER,
Deputy Commissioner.